



भाकृअनुप - केन्द्रीय रोपण फसल अनुसंधान संस्थान  
कासरगोड, केरल - 671 124 भारत  
ICAR - Central Plantation Crops Research Institute  
Kasaragod - 671 124, Kerala, India  
CAE ISO 9001:2008 Certified Institution



Phone (Off) : 04994 - 232333  
Fax : 04994 - 232322  
HPABX : 04994 - 232893 - 95  
04994 - 232090  
04994 - 232996



E-mail : director.eperi@icar.gov.in  
directoreperi@gmail.com  
chowdappa.p@icar.gov.in  
Website : http://www.eperi.gov.in

F.No.40(3)/2017 -Estate

Date :11.09.2017

Shri Mohammed Nuhman,  
PWD Contractor,  
Mogral,  
Kasaragod.

Sub : Work "Repair and maintenance of drainage behind type IV quarters" at CPCRI,  
Kasaragod-reg  
Ref : Your quotation dated 05.08.2017

Sir,

Your quotation cited above to execute the work "Repair and maintenance of drainage behind type IV quarters" at CPCRI, Kasaragod at a total cost of Rs.99,922/- (Rupees ninety nine thousand nine hundred and twenty two only) has been accepted and accordingly the work is hereby awarded to you for execution. You are therefore requested to take up the work and complete the same within **45 days. Further before executing the work copy of GST registration certificate should be furnished to this Institute.** The order is further subject to the following terms and conditions.

**Terms and conditions:**

1. The work should be executed strictly as per the directions from the Technical Officer (Civil Engineering) of the Institute from time to time.
2. The Institute will not be responsible for any loss/damage/casualty suffered by the Contractor while executing the work, provided there wasn't any mistake on the part of the contractor.
3. Any loss or damage etc. caused to the Institute properties while carrying out the work should be made good failing which necessary action will be initiated to recover the cost of the same.
4. No work tools/implements will be supplied by this Institute.
5. The payment will be made only after satisfactory completion of the whole work to our satisfaction & as per specification.
6. No part payment is payable.
7. Non-completion of the work or part thereof for any invalid reasons within the period prescribed is liable for cancellation and no claims for such works will be entertained under any circumstances and deposits made thereof will be forfeited.

Cont... page 2

- Copy to:
8. **Defects liability period:** Performance Security will be released only **after six months** from the date of completion of the work provided that the contractor has attended to all the complaints informed to him within the liability period.
  9. The contractor or his worker should not use the office toilets and should not waste the water from the office building.
  10. Any defective workmanship found shall be rectified at his cost which may include the materials spoilt/wasted paints due to negligence etc.
  11. The contractor shall, on written request of the Director or his representative on the site, immediately dismiss from the work any person employed by him thereon, who may in the opinion of the Director be incompetent or misbehaves himself and such persons shall not again be allowed to work without the written permission of the Director.
  12. On completion of the work it should be ensured that premises & its surroundings are cleaned (including removal of paints fallen etc.)
  13. Income Tax @ 1% of the bill will be deducted from the work bill. GST amount will be deducted from the work bill as per rule.
  14. Prior permission may be obtained for electricity/water facility, if required, subject to payment for the same.
  15. The period of 12 days allowed for carrying out the work will be reckoned after 10 days from the date of receipt of this order.
  16. **The contractor shall debit the Performance Security within 10 days from the issue of work order. The period can be further extended at the written request of the contractor for the period of 10 days with late fee at the rate of 0.1% per day of Performance Security amount.**
  17. The work should be completed within the time limit itself failing which the work order will be cancelled and action taken to complete the remaining work at your risk and cost including forfeiture of security deposit.
  18. In case any extension of time is granted beyond the stipulated period for completion of the work due to any unavoidable genuine circumstances as may be decided by the competent authority, penalty clause to be imposed @ 0.25% **per month** (maximum to 2.5% of the total cost of the work) if work not completed within schedule time or within mutually extended period.
  19. The Director of this Institute reserves the right to reject the work as a whole, if the execution is not satisfactory or does not conform to the approved specification.
  20. In the event of change of address, that may be informed to the office immediately.
  21. If water and electricity is available from the institute by the contract agency then 1.5% of the billed amount shall be deducted from the final bill. If only water supply is available, then 1% of the billed amount shall be deducted. 0.5% in terms of electricity.

You may remit a Performance Security of **Rs.9,922/- (Rupees nine thousand nine hundred and twenty two only)** being the 10% of contract value by DD, FD Receipt or Bank Guarantee from the Commercial Bank in an acceptable form before commencement of the work. The Bid Security deposited along with the tender will be refunded immediately on furnishing the Performance Security (If bank guarantee is produced the period of release of bank guarantee will be given by the office including release of the same).

Please acknowledge receipt of this order and confirm acceptance within 7 days from the date of receipt of this letter.

Yours faithfully,

  
Assistant Administrative Officer (Estate)

Encl: 1. Schedule of work

Cont... page 3

date of  
him

Copy to :

1. The Asst. Labour Commissioner(Central), Office of the Regional Labour Commissioner, Kendriya Shram Sadan, Olimugal, By pass Road, Kakkanad, Kochi 682 030.
2. The Finance and Accounts Officer, CPCRI, Kasaragod. **Head of Account "118202 Repair and Maintenance of Residential buildings" (Non-Plan)2017-18.**
3. The AAO(Bills), CPCRI, Kasaragod.
4. Technical Officer (Civil Engineering) CPCRI, Kasaragod, it may please be ensured that the contractor is permitted to commence the work at the work site immediately on receipt of security deposit. It may be ensured work is completed within the prescribed time and according to the specifications as approved. The date of commencement of the work awarded may be intimated and progress of work reported periodically.
5. CPCRI, Website

1045

Assistant Administrative Officer (Estate)



भाकृअनुप - केन्द्रीय रोपण फसल अनुसंधान संस्थान  
कासरगोड, केरल - 671 124 भारत  
ICAR - Central Plantation Crops Research Institute  
Kasaragod - 671 124, Kerala, India  
[An ISO 9001:2008 Certified Institution]



Phone (OIT) : 04994 - 232333  
Fax : 04994 - 232322  
EPABX : 04994 - 232893 - 95  
04994 - 232090  
04994 - 232996



E-mail : [director.cperi@icar.gov.in](mailto:director.cperi@icar.gov.in)  
[director.cperi@gmail.com](mailto:director.cperi@gmail.com)  
[chowdappa.p@icar.gov.in](mailto:chowdappa.p@icar.gov.in)  
Website : <http://www.cperi.gov.in>

F.No.40(3)/2017 -Estate

Date :11.09.2017

### Description of Work

NAME OF THE WORK: Repair and maintenance of drainage behing type IV quarters at ICAR-CPCRI, KASARAGOD.

SL. NO.	DESCRIPTION OF THE WORK	UNIT	APPROX QUANTITY	Rate	AMOUNT (Rs.)
1	Demolishing brick work manually/by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge. In cement mortar	cum	1.56	1925.00	3003.00
2.	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out othe excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	cum	3.00	500.00	1500.00

3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level: 1:3:6 (1 Cement: 3 coarse sand (zone III): 6 graded stone aggregate 20 mm nominal size). Cum	cum	1.20	12500.00	15000.00
4	Brick work with common burnt clay F.P.S (non modular) bricks of class designation 7.5 in foundation and plinth in : Cement mortar 1:4 (1 Cement : 4 Coarse sand)	cum	4.30	5800.00	24,940.00
5	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement : 4 fine sand)	cum	40.00	375.00	15,000.00
6	Providing and laying R.C.C precast slab in C.C. 1:1.5:3 10 cms thick using clean sieved sand and 20 mm and down size jelly Rate to include centering shuttering (but excluding cost os steel reinforcement) laying, consolidation, curing etc complete as per specification and direction by the Engineer in charge	cumt	2.60	9615.00	24,999.00
7	Reinforcement for R.C.C works including straightening cutting bending all complete. Thermo mechanically treated bars.	Kgs.	240	64.50	15,480.00
<b>Total Amount in Rs.</b>					<b>99,922.00</b>

Amount in words: (Rupees Ninety nine thousand nine hundred and twenty two only)

  
  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_