



भाकृअनुप - केन्द्रीय रोपण फसल अनुसंधान संस्थान  
कासरगोड, केरल - 671 124 भारत  
ICAR - Central Plantation Crops Research Institute  
Kasaragod - 671 124, Kerala, India  
Central Plantation Crops Research Institute



Phone (O/H) : 04994 - 232333  
Fax : 04994 - 232322  
LPABX : 04994 - 232835 - 95  
04994 - 232060  
04994 - 232996



E-mail : director.cpcricar.gov.in  
director.cpcricar@gmail.com  
chowdappa.p@icar.gov.in  
Website : http://www.cpcri.gov.in

F.No.40(2)36(M)/2015-Estate

Dated :- 16.08.2017

Shri Mohammed Rafic. C.A  
PWD Contractor  
Kallangai House  
PO Kudlu  
Kasaragod 671124

Sub:-Work for Repair and renovation to the sliding wooden shutters below working platform of Genetics section in IInd floor of DJ building at CPCRI, Kasaragod :-reg.  
Ref:- Work proposal dated: 07.08.2017 by the Dr V Niral, Pr. Scientist.

Sir,

The work proposal cited above for the work "Repair and renovation to the sliding wooden shutters below working platform of Genetic Section in IInd floor of DJ building at CPCRI, Kasaragod " at a total cost of 14,280/- (Rupees Fourteen thousand two hundred and eighty only) has been accepted and accordingly the work is hereby awarded to you for execution. You are therefore requested to take up the work and **complete the same immediately after receipt of work order.** The order is further subject to the following terms and conditions


Term & Conditions:-

01. The works should be carried out under the supervision of Dr. V Niral, Pr. Scientist & Shri Ajith Kumar, TO (CE), CPCRI, Kasaragod.
02. The Institute will not be responsible for the loss or damage/casualty, if any, while executing the work.
03. The rate quoted shall be valid for a minimum period of six month.
04. The Contractor should obtain certificate of registration under contract labour (Regulation & Abolition) Act 1970, from the Regional Labour Commission (Central) Kochi and comply with all the provision of Act.
05. Payment for service contract will be made on satisfactory completion of work and submission of pre-receipted bill.
06. No work tools/implements will be supplied by this Institute.
07. No part payment is payable.
08. The Director of the Institute reserves the right to reject the work as a whole, if the executing is not satisfactory or does not conform to approved specification.
09. Income Tax will be deducted from the payments due for the work done as per rules.
10. Any misconduct/misbehavior on the part of the person provided by the contractor will not be tolerated and he will have to be replaced immediately
11. Any loss of damage etc. caused to the Institute properties while carrying out the works should be made good or else necessary action will be initiated to recover the same.

PTO.

Please acknowledge receipt of the work order and commence the work immediately.

Yours faithfully



Asst. Administrative Officer(Estate) *TK*

Enclose: Description of work

Copy to :-

01. Dr V Niral, Pr. Scientist, CPCRI, Kasaragod.
02. Shri Ajith Kumar K, Technical Officer (CE), CPCRI, Kasaragod.
03. The Sr. Finance & Account Officer CPCRI, Kasaragod.
04. The DDO, CPCRI, Kasaragod.
05. Institute Website
06. Guard File.



Phone (011) - 04994 - 232333  
Fax - 04994 - 232322  
EPABX - 04994 - 232893 - 88  
04994 - 232100  
04994 - 232896



E-mail: [director@percicar.gov.in](mailto:director@percicar.gov.in)  
[directorpercra@gmail.com](mailto:directorpercra@gmail.com)  
[percra@percra.gov.in](mailto:percra@percra.gov.in)  
Website: <http://www.pecr.gov.in>

F.No. 40(2)36(M)2015-Estate

Date: 16.08.2017

### Description of work

Sl No.	Description of Work	Unit	Approx. Quantity	Rate	Amount
1	Dismantling				
1(a).	Taking out doors, windows and clerestory window shutter (steel or wood) including stacking within 50 meters lead: of area 3 sq. meters and below total 9 shutters	Each	9	90	810.00
2.	Repairs of plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per directions of Engineer-In-Charge. 1 with cement mortar 1:4 (1cement: 4 coarse sand)	Sqmt	1.00	400	400.00
3.	FINISHING Whiter washing with lime to give an even shade to the wall surfaces using best quality super white lime powder, synthetic adhesive and blue pigment and sand papering wherever necessary as per instruction of Engineer: Old work (two or more coats)	Sqmt	22.00	15	330.00
4.	DISTEMPERING with 1 <sup>st</sup> quality acrylic distemper (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufactures' specification. The work shall include cleaning the surface of dirt/dust and foreign matter, sand papering including cost and conveyance of all materials, labour, scaffolding, cleaning paint stain from walls, floor etc complete as per specification and direction old work	Sqmt	5.00	49	245.00

	(one or more coats)				
5.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade to the wooden surfaces. The work shall include cleaning the surface of dirt/dust and foreign matter, sand papering including cost and conveyance of all materials, labour, scaffolding, cleaning paint specification and direction One or more coats on old work	Sqmt	28.00	75	2100.00
6.	Providing and fixing Powder coated aluminum work for sliding shutter over existing wooden frames below working platform with extruded built up standards tubular and other sections of approved make and conforming to IS733 and IS 1285 sections medium sections anodized of Jindal/ Hindalco make medium guage dyed to required shade fixed with Rawl plugs and screws or with fixing clips or with expansion fold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/Neoprene felt etc. Two track Aluminum sections shall be smooth, rust free, straight and jointed mechanically wherever required including cleat angle, aluminum snap beading for glazing/paneling, Panelling shall be of Sintex/polypan fillings of 6mm thick of approved color and the directions of Engineer in Charge	Sqmt	3.30	3150	10395.00
Grand Total					<b>14,280.00</b>

**(Rupees Fourteen thousand two hundred and eighty only)**

*Jeyp Singh*

सहायक प्रशासनिक अधिकारी (पुणे)  
Assistant Administrative Officer (Pune) T/c  
केन्द्रीय वनस्पति संशोधन संस्थान  
Central Plantation Crops Research Institute  
कासबागड, बेरार, कर्नाटक - 571 124, India