



भा.कृ.अनु.प. - केन्द्रीय रोपण फसल अनुसंधान संस्थान  
 प्रादेशिक केन्द्र, कृष्णपुरम (डाक), कायमकुलम, केरल 690 533, भारत  
**ICAR - CENTRAL PLANTATION CROPS RESEARCH INSTITUTE**  
 REGIONAL STATION, KRISHNAPURAM (PO), KAYAMKULAM 690 533,  
 KERALA, INDIA  
 (An ISO 9001:2008 Certified Institution)



Phone : PABX : 0479-2442104; 0479 - 2442160 Head : 0479-2442004 Fax: 0479-2445733

Email: headrskgm.cpcri@icar.gov.in, headcpcri@yahoo.co.in Website: http://www.cpcri.gov.in/

F.No. 2 (5)R & M/GENL./EST./2015-2016

DATED :20-01-2016

To

Sub: Quotation for removal of the existing concrete/rock pillars, damaged barbed wire and erection of angle iron pillar and fixing of chain link at ICAR-CPCRI Regional Station, Kayamkulam – reg.

Sir,

Sealed Quotations are invited from Registered Contractors/Agencies/Service providers having valid license/registration, PAN card etc. for carrying out the following works this Regional Station on contract basis.

1. Removal of existing concrete/rock pillars and barbed wire.
2. Erection of angle iron pillar of size 1 ½" x 1 ½" (Inch) 6mm thickness on cement concrete base of size 45cm x 45cm) at a height as mentioned below:
3. Fixing of chainlinks in the pillars by spot welding/tying.

S. No.	Block	Area	Required height above the ground level	Required height below the ground level	Equal width	Required pillars approximately
01.	IX	Four Sides – Total 563 m	2.0 m height	45cm.	2 m	283 Nos.
02.	VI	Along the road side – Total 267 m	2.0 m height	"	"	134 Nos.
03.	V	Along the road side – Total 675 m	1.7 m height	"	"	338 Nos.
04.	IV	Along the oad side – Total 399 m	1.7 m height	"	"	200 Nos.
05.	1	Meterology plot – Total 282 m	1.7 m height	"	"	143 Nos.


4. Transporting of the old concrete rock/pillars to Farm office premises.

**Terms & Conditions:-**

1. The detailed plan of work should be clearly indicated in the quotation
2. Necessary chain links will be supplied by Office. Galvanized angle iron as per specifications and all other raw materials for fixing chain links for carrying out the above works should be brought by the contractor at his own cost.
3. The amount quoted should be indicated both in figures and words and should be valid for at least 90 days.
4. The works should be undertaken as per the directives of the OIC/Tech.Officer (Farm).
5. Income Tax as per rule will be deducted from the contractor's bill for which PAN number should be furnished on the quotation.

PTO

6. This work does not confer any claim or right for future regular employment at this Station.
7. The Contracting Agency shall comply with the provisions of Central Contract Labour (Regulations and Abolition) Act, Minimum wage Act, EPF Act/ESI Act/ etc. and maintain/produce all records to the concerned Authority should be furnished within one month of the date of receipt of order.
8. The contractor must ensure safety precautions for the workers and CPCRI will not entertain any compensation on accident or injury, if any, occurred to the workers during the course of completing this work.
9. The right to accept or reject all or any of the quotation rests with the Head of this Station.
10. Quotation should be sealed and Superscribed as "Quotation for removal of the existing concrete/ rock pillars, damaged barbed wire etc. under Farm Section" and reach this office on or before 30-01-2016.

  
(Pradeepkumar Vasu)  
Asstt. Administrative Officer

Copy to :

- 01 The Asstt. Finance & Accounts Officer, CPCRI (RS), Kayamkulam
- 02 SIC/<sup>Farm</sup>Tech. Officer, CPCRI (RS), Kayamkulam
- 03 The Secretary, Krishnapuram Grama Panchayat, Krishnapuram
- 04 The Village Officer, Krishnapuram Village, Krishnapuram
- 05 The Secretary, Kayamkulam Municipality, Kayamkulam
- 06 ✓ Dr. C.K. Nampoothiri, ACTO (Statistics) for putting the same in ICAR-CPCRI Website

With a request to display this Notice in their notice boards