



भाकृअनुप - केन्द्रीय रोपण फसल अनुसंधान संस्थान
कासरगोड, केरल - 671 124 भारत
ICAR - Central Plantation Crops Research Institute
Kasaragod - 671 124, Kerala, India
ICAR (ISI) - ISO 9001:2008 Certified Institute



Phone (00) 04994 - 232323
Fax 04994 - 232322
CIVILS 04994 - 232885 - 95
04994 - 232090
04994 - 232090



E-mail : director.epcri@icar.gov.in
director.epcri@gnitail.com
chowdappa@icar.gov.in
Website : <http://www.epcri.gov.in>

F.No.40(3)-2018 -Estate

Date :21.04.2018

Mr. Mohammed Nuhman
CPWD Contractor
Azad Manzil
Mogral PO, Kumbla Via,
Kasaragod.

Sub : Work "Deepening the bore well near Second Gate of Hill block campus at CPCRI, Kasargod - reg
Ref : Your quotation dated 06.04.2018

Sir,

Your quotation cited above to execute the work "**Deepening the bore well near Second Gate of Hill block campus at CPCRI, Kasargod**" at a total cost of Rs. 88,998/- (Rupees **Eighty eight thousand nine hundred ninety eight** only including tax) has been accepted and accordingly the work is hereby awarded to you for execution. You are therefore requested to take up the work and complete the same within **15 days**. The order is further subject to the following terms and conditions.

Terms and conditions:

1. The work should be executed strictly as per the directions from the Shri Rajendran Nair, Technical Officer (Mechanical Engineering) of the Institute from time to time.
2. The Institute will not be responsible for any loss/damage/casualty suffered by the Contractor while executing the work, provided there wasn't any mistake on the part of the contractor.
3. Any loss or damage etc. caused to the Institute properties while carrying out the work should be made good failing which necessary action will be initiated to recover the cost of the same.
4. No work tools/implements will be supplied by this Institute.
5. The payment will be made only after satisfactory completion of the whole work to our satisfaction & as per specification.
6. No part payment is payable.
7. Non-completion of the work or part thereof for any invalid reasons within the period prescribed is liable for cancellation and no claims for such works will be entertained under any circumstances and deposits made thereof will be forfeited.

Cont... page 2

8. **Defects liability period:** Performance Security will be released only **after six months** from the date of completion of the work provided that the contractor has attended to all the complaints informed to him within the liability period.
9. The contractor or his worker should not use the office toilets and should not waste the water from the office building.
10. Any defective workmanship found shall be rectified at his cost which may include the materials spoilt/wasted paints due to negligence etc.
11. The contractor shall, on written request of the Director or his representative on the site, immediately dismiss from the work any person employed by him thereon, who may in the opinion of the Director be incompetent or misbehaves himself and such persons shall not again be allowed to work without the written permission of the Director.
12. On completion of the work it should be ensured that premises & its surroundings are cleaned (including removal of paints fallen etc.)
13. Income Tax will be deducted as per rule from the work bill. GST and other tax if applicable will be paid directly to the concerned department by the contractor as per rule and same show in final bill. Further after remittance copy of the same should be furnished at this Office. The performance security amount will be release after remit the same.
14. Prior permission may be obtained for electricity/water facility, if required, subject to payment for the same.
15. The period of 15 days allowed for carrying out the work will be reckoned after 10 days from the date of receipt of this order.
16. **The contractor shall debit the Performance Security within 10 days from the issue of work order. The period can be further extended at the written request of the contractor for the period of 10 days with late fee at the rate of 0.1% per day of Performance Security amount.**
17. The work should be completed within the time limit itself failing which the work order will be cancelled and action taken to complete the remaining work at your risk and cost including forfeiture of security deposit.
18. In case any extension of time is granted beyond the stipulated period for completion of the work due to any unavoidable genuine circumstances as may be decided by the competent authority, penalty clause to be imposed @ 0.25% **per month** (maximum to 2.5% of the total cost of the work) if work not completed within schedule time or within mutually extended period.
19. The Director of this Institute reserves the right to reject the work as a whole, if the execution is not satisfactory or does not conform to the approved specification.
20. In the event of change of address, that may be informed to the office immediately.
21. If water and electricity is available from the institute by the contract agency then 1.5% of the billed amount shall be deducted from the final bill. If only water supply is availed, then 1% of the billed amount shall be deducted. 0.5% in terms of electricity.

You may remit a Performance Security of **Rs. 8900/- (Rupees Eight thousand nine hundred only)** being the 10% of contract value by DD, FD Receipt or Bank Guarantee from the Commercial Bank in an acceptable form before commencement of the work. The Bid Security deposited along with the tender will be refunded immediately on furnishing the Performance Security (If bank guarantee is produced the period of release of bank guarantee will be given by the office including release of the same).

Please acknowledge receipt of this order and confirm acceptance within 7 days from the date of receipt of this letter.

Yours faithfully,
Sd/-
Administrative Officer


Encl: 1. Schedule of work & Special Term and Conditions.

Cont... page 3

py to :

1. The Asst. Labour Commissioner(Central), Office of the Regional Labour Commissioner, Kendriya Shram Sadan, Olimugal, By pass Road, Kakkanad, Kochi 682 030.
2. The Finance and Accounts Officer, CPCRI, Kasaragod. **Head of Account "118203 Repair and Maintenance (Minor works) (Revenue)2018-19.**
3. The AAO(Bills), CPCRI, Kasaragod.
4. Shri Rajendran Nair, Technical Officer (Mechanical Engineering) CPCRI, Kasaragod, it may please be ensured that the contractor is permitted to commence the work at the work site immediately on receipt of security deposit. It may be ensured work is completed within the prescribed time and according to the specifications as approved. The date of commencement of the work awarded may be intimated and progress of work reported periodically.
5. CPCRI, Website

636 ✓


Administrative Officer



ಕರ್ನಾಟಕ ಸರ್ಕಾರ
ಕೆ.ಆರ್.ಪೇಟೆ
ಕೆ.ಆರ್.ಪೇಟೆ

ಕರ್ನಾಟಕ ಸರ್ಕಾರ
ಕೆ.ಆರ್.ಪೇಟೆ
ಕೆ.ಆರ್.ಪೇಟೆ



F.No. 40(3)/ 2018-Estate


Dated : 17.04.2018

Description of Work

Name of the Work: Deepening the bore well near Second Gate of Hill block campus at CPCRI, Kasargod.

Sl.No	Description of the work	Unit	Approx. Qty.	Rate	Amount (Rs.)
1	Lifting the bore well motor from the bore well Removing of submersible pump set and GI pipe at existing bore well etc complete.	Each	1	5000.00	5000.00
2	Deepening the borewell from the Existing depth of 160”(49m) Deepening of existing bore well including transportation from one place to another and in all alluvial soil sedimentary strata and stand stone, shale, pebbles boulders etc, By first taking a pilot bore of 165mm dia vertical bore and then enlarging to required dia direct or reverse rotary mud circulation method using rotary rigs, fuel, labour and drilling behtonite and water required for drilling at site and including construction of mud pit etc complete complying with standard specification.	RMT	36	742.75	26739.00
3	2.5” TATA B Class GI Pipe Supply and fitting and installing of 2.5” (63.5MM) Outer Diameter) G.I delivery pipe of “B “CLASS ISI Mark (Tata or Equivalent) with all flanges ,bends , Tees Offet showers ,gratings etc including fitting the joints , fixing in position and erection of pump set including accessories, testing and commissioning of pump sets etc complete as directed	RMT	36	838.65	30191.40
4	Providing and laying of 3core, 4mm2 flat submersible pump cable with copper wires of electrolytic grade conductor conforming to general specification as per IS:694 latest edition from submersible pump to electrical panel including water proofing cable joints as per requirement complete in all respect as per direction of engineer-in-charge.(Finolex/Polycab/,L&T)	RMT	90	136.00	12240.00


5	Fitting /erecting the motor pump set in the Borewell Installation for the erection of submersible pump set in bore well including fixing and jointing submersible cable with proper clamps up to the starter to the required depth and also fixing of riser pipes to the required depth values erection clamps, laying and jointing the cables and twin earthing as per IE rules etc. complete testing pump sets and as directed by Technical Officer .	Each	1	7828.00	7828.00
6	Closing the nearest Borewell with sand and concrete Providing and laying cement concrete work in 1:3:6 using 20mm and downsize coarse aggregate for sealing the drilled bore well hole to seal the upward entry of water including clay/sand packing Sand/ clay filling 10 mtr from bottom and 6Mtr concrete in the centre portion as required in proper manner as directed.	JOB	JOB	7000.00	7000.00
Grand total including GST @ 12%					88998.00


 प्रयोगिक अधिकारी (सहायक) ...
 केंद्राध्यक्ष, कृषि विज्ञान संस्थान, ...
 Central Plantation Crops Research Institute, ...

TERMS AND CONDITIONS (निबंधन और शर्तें)

SPECIAL TERMS AND CONDITIONS

- 1). Deeping of existing borewell of 165mm dia bore finished form surface to bottom.
- 2). Supplying 3 cores flat 4mm 2 copper cable.(Finolex/Polycab/,L&T) make.
- 3.) Supplying, fitting and installing the 65mm nominal bore of GI medium duty pipes ISI mark with all flanges, bends, tees, junctions, offset shows, gratings etc., including fitting the joints fixing in position with clamps nails spacers etc
- 4). Supplying, fitting and installing all accessories as per the schedule of item.,the said job has to be completed within limited period of 15 DAYS
- 5 The contractor shall appoint an authorized representative at site to get day to day instructions from the Engineer-in-Charge.
- 6.) The contractor will be responsible for getting the gate passes of worker issued from competent authority and will surrender these gates passes on completion of work
- 7.) If the contractor fails to start/take-up/complete the work & continues to give the poor progress & poor quality of work, The Institute shall be entitled to get the work done departmentally or from any other agency at the risk & cost of the contractor after serving a notice of 3 days to the contractor without prejudice to other provision of the contract.
- 8). The work shall be executed as per instruction of Engineer-In-Charge and to complete the work as per schedule given to him in view of availability of shut down period of unit.
- 9). Arrangement of electricity/generator for development of borewell will be in the scope of contractor for testing and commissioning of submersible pumps and bore wells only. Contractor will also make his own arrangements for extension of electrical supply system from that point to other site of work as per requirement. The contractor shall make his own arrangement of water at site for carrying out the work.
- 10). All the consumable such as cement, stone-dust, fine sand, bricks, stone bajri etc. if required shall be arranged by contractor himself & should be of CPWD specifications. Cement to be used will be of ISI mark/reputed make (Ordinary Portland Cement).


प्रशासनिक अधिकारी, Administrative Officer
केन्द्रीय नगरपालिका कार्यालय, काठमाडौं
Central Panchayat Office, Kathmandu, Nepal