



भाकृअनुप - केन्द्रीय रोपण फसल अनुसंधान संस्थान  
कासरगोड, केरल - 671 124 भारत  
ICAR - Central Plantation Crops Research Institute  
Kasaragod - 671 124, Kerala, India  
(An ISO 9001:2008 Certified Institution)



Phone (Off) : 04994 - 232333  
Fax : 04994 - 232322  
LPBX : 04994 - 232803 - 95  
04994 - 232090  
04994 - 232996

E-mail : director@peri@icar.gov.in  
directoreperi@gmail.com  
chowdappa@icar.gov.in  
Website : <http://www.peri.gov.in>

F.No.40(3)-2018 -Estate

Date :11.05.2018

**Shri Mqhammed Rafic C.A,**  
**PWD Contractor,**  
**Kallangai House,**  
**Kasaragod 671 124.**

Sub : Work "Partitioning the Laminar flow room inside the corridor with aluminium sliding door for entamology lab at DJ Building, C.P.C.R.I., Kasaragod" - reg  
Ref : Your quotation dated 28.03.2018.

Sir,

Your quotation cited above to execute the work "Partitioning the Laminar flow room inside the corridor with aluminium sliding door for entamology lab at DJ Building C.P.C.R.I., Kasaragod at a total cost of Rs. 48,468/- (Rupees Forty Eight thousand four hundred sixty eight only including tax) has been accepted and accordingly the work is hereby awarded to you for execution. You are therefore requested to take up the work and complete the same within 30 days. The order is further subject to the following terms and conditions.

**Terms and conditions:**

1. The work should be executed strictly as per the directions from the Shri Ajith Kumar, Technical Officer (Civil Engineer) of the Institute from time to time.
2. The Institute will not be responsible for any loss/damage/casualty suffered by the Contractor while executing the work, provided there wasn't any mistake on the part of the contractor.
3. Any loss or damage etc. caused to the Institute properties while carrying out the work should be made good failing which necessary action will be initiated to recover the cost of the same.
4. No work tools/implements will be supplied by this institute.
5. The payment will be made only after satisfactory completion of the whole work to our satisfaction & as per specification.
6. No part payment is payable.
7. Non-completion of the work or part thereof for any invalid reasons within the period prescribed is liable for cancellation and no claims for such works will be entertained under any circumstances and deposits made thereof will be forfeited.
8. Not less than minimum rate of wages fixed for the respective category should be paid to the workers. All requirements under labour laws should be fulfilled.

Cont... page 2

9. **Defects liability period:** Performance Security will be released only **after six months** from the date of completion of the work provided that the contractor has attended to all the complaints informed to him within the liability period.
10. The contractor or his worker should not use the office toilets and should not waste the water from the office building.
11. Any defective workmanship found shall be rectified at his cost which may include the materials spoilt/wasted paints due to negligence etc.
12. The contractor shall, on written request of the Director or his representative on the site, immediately dismiss from the work any person employed by him thereon, who may in the opinion of the Director be incompetent or misbehaves himself and such persons shall not again be allowed to work without the written permission of the Director.
13. On completion of the work it should be ensured that premises & its surroundings are cleaned (including removal of paints fallen etc.)
14. Income Tax will be deducted as per rule from the work bill. GST and other tax if applicable will be paid directly to the concerned department by the contractor as per rule and same show in final bill. Further after remittance copy of the same should be furnished at this Office. The performance security will be release after remit the same.
15. Prior permission may be obtained for electricity/water facility, if required, subject to payment for the same.
16. The period of 30 days allowed for carrying out the work will be reckoned after 10 days from the date of receipt of this order.
17. **The contractor shall debit the Performance Security within 10 days from the issue of work order. The period can be further extended at the written request of the contractor for the period of 10 days with late fee at the rate of 0.1% per day of Performance Security amount.**
18. The work should be completed within the time limit itself failing which the work order will be cancelled and action taken to complete the remaining work at your risk and cost including forfeiture of security deposit.
19. In case any extension of time is granted beyond the stipulated period for completion of the work due to any unavoidable genuine circumstances as may be decided by the competent authority, penalty clause to be imposed @ 0.25% per month (maximum to 2.5% of the total cost of the work) if work not completed within schedule time or within mutually extended period.
20. The Director of this Institute reserves the right to reject the work as a whole, if the execution is not satisfactory or does not conform to the approved specification.
21. In the event of change of address, that may be informed to the office immediately.
22. If water and electricity is availed from the institute by the contract agency then 1.5% of the billed amount shall be deducted from the final bill. If only water supply is availed, then 1% of the billed amount shall be deducted. 0.5% in terms of electricity.

You may remit a Performance Security of **Rs. 4847/- (Rupees Four thousand eight hundred forty seven only)** being the 10% of contract value by DD, FD Receipt or Bank Guarantee from the Commercial Bank in an acceptable form before commencement of the work. The Bid Security deposited along with the tender will be refunded immediately on furnishing the Performance Security (If bank guarantee is produced the period of release of bank guarantee will be given by the office including release of the same).


Please acknowledge receipt of this order and confirm acceptance within 7 days from the date of receipt of this letter.

Yours faithfully,  
Sd/-

Copy to :

1. The Asst. Labour Commissioner(Central), Office of the Regional Labour Commissioner, Kendriya Shram Sadan, Olimugal, By pass Road, Kakkanad, Kochi 682 030.
2. The Finance and Accounts Officer, CPCRI, Kasaragod. **Head of Account "118201 Repair and Maintenance (Office Building ) (Revenue)2018-19.**
3. The AAO(Bills), CPCRI, Kasaragod.
4. Shri Ajith Kumar, Technical Officer (Civil Engineer) CPCRI, Kasaragod, it may please be ensured that the contractor is permitted to commence the work at the work site immediately on receipt of security deposit. It may be ensured work is completed within the prescribed time and according to the specifications as approved. The date of commencement of the work awarded may be intimated and progress of work reported periodically.
5. CPCRI, Website

1677  
5

  
Asst. Administrative Officer



Schedule of Work

Name of the Work: Partitioning the Lamina flow room inside the corridor with aluminium sliding door for entamology lab at DJ Building C.P.C.R.I., Kasaragod – 671 124.

Sl.No	Description of the work	Unit	Approx. Qty.	Rate	Amount (Rs.)
1	Charges towards removing the sliding door from the inner side of Lamina floor room and refitting to the outer portion . The rate shall include cost and conveyance of all materials , removing , refixing to original finish as directed	Set	1	750.00	750.00
2)	Providing/fabricating/assembling and fixing Anodized aluminum Fixed partition to the lamina floor room inside corridor using Jindal make medium Weight aluminium section as follows:- Horizontal members Size – 63.50 x 38.10 mm at 0.75 kg/m.c/c spacing shall not exceed 90 cm vertical members size – 63.50 x 38.10mm at 0.75 kg/m.c/c spacing shall not be more Than 90 cm/bottom portion – 3’ height portion – PVC Sections of matching color to be used as fillings for bottom section 6mm thick Including necessary clips, Rubber beading Aluminium Beading and fixing to the Adjoining/existing wall/partition etc. Top portion 5mm thick plain glass/grounded glass with all necessary fittings/fixtures etc., complete as directed.	Sqmt	10.12	3900.00	39468.00
3)	<b>Aluminium Sliding door</b> Providing/fabricating/assembling and fixing nodized aluminum sliding door type – plain sliding door to the existing aluminium partition using jindal make medium weight aluminium sections medium weight as follows:- Vertical, top and centre member shall be size 47.62 mm x 44.45 mm and bottom members shall be 114.3 x 44.45 mm top portion – with plain glass 5 mm thick/grounded glass, bottom portion 3’ height Sintex 6mm thick PVC Profiles, guide rails ‘C’ heavy section etc.. The work including necessary clips, rubber beading aluminium triangular beading, locks, hinges, door stoppers handles on both the sides etc., complete and fixing to the adjoining members wall/frame work with all necessary fittings/ fixture etc., complete Sliding door 1 x 1.10 x 2.00 =2.200 Say 2.20Sqmt	Sqmt	2.20	3750.00	8250.00
<b>Grand Total Rs.</b>					<b>48,468.00</b>

(Rupees Forty Eight Thousand four hundred sixty eight only)