



भा.कृ.अनु.प. - केन्द्रीय रोपण फसल अनुसंधान संस्थान
प्रादेशिक केन्द्र, कृष्णपुरम (डाक), कायमकुलम, केरल 690 533, भारत
ICAR - CENTRAL PLANTATION CROPS RESEARCH INSTITUTE
REGIONAL STATION, KRISHNAPURAM (PO), KAYAMKULAM 690 533,
KERALA, INDIA
(An ISO 9001:2008 Certified Institution)



Phone : PABX : 0479-2442104; 0479 - 2442160 Head : 0479-2442004 Fax: 0479-2445733
Email: headrskgm.cpcri@icar.gov.in, headcpcri@yahoo.co.in Website: http://www.cpcri.gov.in/

F. No. 2(5) R & M/GENL.2017-18/VOL.IV

DATED: 19-04-2017

To

Sub: Quotation for erection of angle iron pillar and fixing of chain link at ICAR-CPCRI Regional Station, Kayamkulam – reg.

Sir,

Sealed Quotations are invited from Registered Contractors/Agencies/Service providers having valid license/registration, PAN card etc. for carrying out the following works this Regional Station on contract basis.

1. Erection of angle iron pillar of size 2" x 2" (Inch) 6mm thickness/GI pipe 1.5" (B Class) on cement concrete base of size 30cm x 30cm) at a height as mentioned below:
2. Top fixing and leveling with ¾" X ¾" (3mm) angle iron.
3. Fixing of chain links in the pillars by spot welding
4. 2 pieces of 15cm cross bar are to be welded across the bottom portion of the GI Pipe/Angle iron)

Sl. No.	Block	Area	Required height above the ground level	Required height below the ground level	Equal width	Required pillars (approximately)
02.	VI	Along the road side –Total 267m	2.0 m height	30 cm	2m	134 Nos.
03.	V	Along the road side –Total 675m	1.7 m height	"	"	338 Nos.
04.	IV	Along the road side –Total 399m	1.7 m height	"	"	200 Nos.

Terms & Conditions:-

1. The detailed plan of work should be clearly indicated in the quotation.
2. Necessary chain links will be supplied by Office. Galvanized angle iron as per specifications and all other raw materials for fixing chain links for carrying out the above works should be brought by the contractor at his own cost.

P.T.O

3. EMD of Rs.7000/- (Rupees Seven thousand only) in the form of DD should be drawn in favour of ICAR UNIT, CPCRI (RS), KAYAMKULAM, and enclosed with quotation.
4. The amount quoted should be indicated both in figures and words and should be valid for at least 90 days.
5. The works should be undertaken as per the directives of the OIC/Tech. Officer (Farm).
6. Income Tax as per rule will be deducted from the contractor's bill for which PAN number should be furnished alongwith the quotation.
7. This work does not confer any claim or right for future regular employment at this Station. The Contracting Agency shall comply with the provisions of Central Contract Labour (Regulations and Abolition) Act, Minimum wage Act, EPF Act/ESI Act/ etc. and maintain/produce all records to the concerned Authority should be furnished within one month of the date of receipt of order.
8. The contractor must ensure safety precautions for the workers and CPCRI will not entertain any compensation on accident or injury, if any, occurred to the workers during the course of completing this work.
9. The right to accept or reject all or any of the quotation rests with the Head of this Station.
10. Quotation should be sealed and Superscribed as "Quotation for fixing of chain link at CPCRI, (RS) Kayamkulam and reach this office on or before 11-05-2017.


Asstt. Administrative Officer

Copy to:

1. The Asstt. Finance & Accounts Officer, CPCRI (RS), Kayamkulam
2. SIC/Tech.Officer, CPCRI (RS), Kayamkulam
3. The Secretary, Krishnapuram Grama Panchayat, Krishnapuram
4. The Village Officer, Krishnapuram Village, Krishnapuram
5. The Secretary, Kayamkulam Municipality, Kayamkulam
6. Dr.C.K. Nampoothiri, ACTO (Statistics) for putting the same in ICAR-CPCRI Website.

With a request to display this Notice in there Notice Boards.

Sl. No.	Block Area	Required height above the ground level	Required height below the ground level	Equal width pillars (approximate)	Equal Required
04	Along the road side - Total 399m	1.7 m height		200 Nos.	
03	Along the road side - Total 675m	1.7 m height		338 Nos.	
02	Along the road side - Total 207m	2.0 m height	30 cm	144 Nos.	

Terms & Conditions:

1. The detailed plan of work should be clearly indicated in the quotation.
2. Necessary chain links will be supplied by Office. Galvanized angle iron as per specifications and all other raw materials for fixing chain links for carrying out the above works should be brought by the contractor at his own cost.